



Wolstenholme, Joshua M. ORCID logoORCID:
<https://orcid.org/0000-0001-9244-7210>, Skinner, Chris, Milan,
David, Thomas, Robert E. and Parsons, Daniel R. ORCID
logoORCID: <https://orcid.org/0000-0002-5142-4466> (2025) Hydro-
geomorphological modelling of leaky wooden dam efficacy from
reach to catchment scale with CAESAR-Lisflood 1.9j. Geoscientific
Model Development, 18 (5). pp. 1395-1411.

Downloaded from: <https://ray.yorks.ac.uk/id/eprint/14242/>

The version presented here may differ from the published version or version of record. If
you intend to cite from the work you are advised to consult the publisher's version:

<https://doi.org/10.5194/gmd-18-1395-2025>

Research at York St John (RaY) is an institutional repository. It supports the principles of
open access by making the research outputs of the University available in digital form.
Copyright of the items stored in RaY reside with the authors and/or other copyright
owners. Users may access full text items free of charge, and may download a copy for
private study or non-commercial research. For further reuse terms, see licence terms
governing individual outputs. [Institutional Repositories Policy Statement](#)

RaY

Research at the University of York St John

For more information please contact RaY at
ray@yorks.ac.uk



Hydro-geomorphological modelling of leaky wooden dam efficacy from reach to catchment scale with CAESAR-Lisflood 1.9j

Joshua M. Wolstenholme^{1,2}, Christopher J. Skinner^{3,2}, David Milan⁴, Robert E. Thomas², and Daniel R. Parsons¹

¹Geography and Environment, Loughborough University, Loughborough, UK

²Energy and Environment Institute, University of Hull, Hull, UK

³FloodSkinner, York, UK

⁴School of Environmental Sciences, University of Hull, Hull, UK

Correspondence: Joshua M. Wolstenholme (j.m.wolstenholme@lboro.ac.uk)

Received: 9 July 2024 – Discussion started: 30 August 2024

Revised: 18 December 2024 – Accepted: 15 January 2025 – Published: 5 March 2025

Abstract. Leaky wooden dams (LDs) are woody structures installed in headwater streams that aim to reduce downstream flood risk through increasing in-channel roughness and decreasing river longitudinal connectivity in order to desynchronise flood peaks within catchments. Hydrological modelling of these structures omits sediment transport processes since the impact of these processes on flow routing is considered negligible in comparison to in-stream hydraulics. Such processes are also excluded on the grounds of computational expense. Here we present a study that advances our ability to model leaky wooden dams through a roughness-based representation in the landscape evolution model CAESAR-Lisflood, introducing a flexible and representative approach to simulating the impact of LDs on reach and broader catchment-scale processes. The hydrological and geomorphological sensitivity of the model is tested against grid resolution and variability in key parameters such as leaky dam gap size and roughness. The influence of these parameters is also tested in isolation from grid resolution whilst evaluating the impact of simulating sediment transport on computational expense, model domain outputs, and internal geomorphological evolution. The findings show that simulating sediment transport increased the volume of water stored in the test reach (channel length of 160 m) by up to an order of magnitude, whilst it reduced discharge by up to 31 % during a storm event (6 h, 1-in-10-year event). We demonstrate how this is due to the leaky dam acting to induce geomorphic change and thus increasing channel roughness. When considering larger grid resolutions, however, our results show that care must be due to overesti-

mations of localised scour and deposition in the model and that behavioural approaches should be adopted when using CAESAR-Lisflood in the absence of robust empirical validation data.

1 Introduction

Natural flood management (NFM) seeks to emulate natural processes to reduce flood risk through the attenuation of water, that is, “slowing the flow” by desynchronising tributaries, reducing surface runoff and/or improving channel–floodplain connectivity (SEPA, 2015; Burgess-Gamble et al., 2017; Lane, 2017). NFM is becoming increasingly popular with flood risk managers due to its multiple benefits and perceived low risk; however, due to altering the hydrological regime, there is potential for structures to become displaced and washed out (e.g. Nisbet et al., 2015). NFM is also an effective method to engage local communities and land users in potentially reducing flood risk (Burgess-Gamble et al., 2017; Dadson et al., 2017; Newson et al., 2021). Reintroduction of wood to the river channel is a popular form of NFM, employed for multiple co-benefits, such as habitat creation and ecological enhancements (e.g. Wohl, 2017; Ockelford et al., 2024) as well as flood peak reduction (e.g. van Leeuwen et al., 2024; Villamizar et al., 2024). As a result, NFM now accounts for approximately 20 % of UK river restoration projects (Cashman et al., 2018; Grabowski et al., 2019).

One method of introducing wood is through building leaky wooden dams (LDs). LDs are a form of in-channel blockage that can be installed either within a river channel (Metcalf et al., 2017; Deane et al., 2021) or as a runoff attenuation feature (RAF), intersecting surface runoff pathways (Nicholson et al., 2012; Nicholson et al., 2019) in an effort to reduce flow velocity and reduce flood risk, increase biodiversity, and improve river heterogeneity (Burgess-Gamble et al., 2017). LDs aim to emulate natural woody debris found in river channels by partially or completely blocking the channel to accelerate the recruitment of natural wood as part of the natural wood cycle (Gregory et al., 1985; Addy and Wilkinson, 2016). LDs have multiple benefits including (but not limited to) improving water quality, increasing habitat diversity, flood wave attenuation, and increasing floodplain connectivity (Wenzel et al., 2014; Burgess-Gamble et al., 2017; Grabowski et al., 2019).

Despite their rapid deployment in riverine management over recent years, a key knowledge gap is how LD efficacy evolves temporally in response to both geomorphic evolution up- and downstream of the LD and also flood sequences (Addy and Wilkinson, 2019; Grabowski et al., 2019). The influence of large wood on river systems is well understood: wood increases fluvial complexity whilst being resistant to transportation and providing storage space for water through increasing floodplain connectivity and creating out-of-bank storage (Gurnell et al., 2018; Wohl et al., 2019). Specifically, large wood can form pools (e.g. Abbe and Montgomery, 1996; Al-Zawaidah et al., 2021; Ravazzolo et al., 2022), increase sediment storage (e.g. Comiti et al., 2008; Wohl and Beckman, 2014), protect against or induce bank erosion (e.g. Abbe et al., 2018; Galia et al., 2024), and influence floodplain morphology (e.g. Sear et al., 2010; Wohl, 2013). Large wood is generally mobile (Wohl et al., 2023) unlike LDs, which are often engineered and anchored in situ and therefore can be functionally different with wide-ranging designs (Lashford et al., 2022; Lo et al., 2022; Quinn et al., 2022).

Challenges in disentangling the relative impact of LDs from the influence of land use, antecedent conditions, and other flood risk management (FRM) interventions presently result in an unclear understanding of their influence over time. Similarly to natural wood, LDs influence the hydraulic regime through increasing roughness and thus have the potential to influence channel geomorphology. The few empirical field studies that have focussed on LDs have highlighted that LDs can reduce peak flows for the 1-year annual exceedance probability (AEP) by 10% on average; however, the response can be highly variable (van Leeuwen et al., 2024). Norbury et al. (2021) reported an average reduction in peak discharge of 27.3%. The backwater rise induced by LDs is also variable and can be increased or decreased with the presence of porosity-reducing material (Muhawenimana et al., 2023). Furthermore, the ability of a LD to store water, or sediment, can be dependent on the distance between the riverbed and the bottom of the LD, with gaps > 0.3 m

unable to store sediment in the Yorkshire Dales, UK (Lo et al., 2022), while increased wood volume also amplifies scour (Schalko et al., 2019). Laboratory experiments have shown that representing LDs as non-porous structures increases drag and flow area (Muhawenimana et al., 2021), and therefore it is important to account for porosity of the structures in numerical simulations. Yet often porosity is not considered in numerical simulations due to representing these complex structures in reduced-complexity models.

Recent works have focused on integrating LDs into 1D and 2D models at different spatial scales (Hill et al., 2023), most commonly representing the interventions as localised roughness adjustments (Pinto et al., 2019; Geertsema et al., 2020), geometry adjustments (Pearson, 2020; Walsh et al., 2020), or a combination of the two (Dixon et al., 2016; Senior et al., 2022). LDs have also been represented in hydraulic models through stage–discharge relationships realising LDs (and other RAFs) as weirs or culverts (Thomas and Nisbet, 2012; Metcalfe et al., 2017; Keys et al., 2018; Hankin et al., 2019, 2020; Pinto et al., 2019; Leakey et al., 2020; Pearson, 2020; Follett and Hankin, 2022). A comprehensive review of the large wood numerical modelling literature focused on artificially placed wood can be found in Addy and Wilkinson (2019).

The vast majority of numerical models used for LD evaluation have not considered the impacts of sediment transport on function and efficacy. This is in line with operational approaches to modelling flood risk, where sediment transport processes have often been considered a negligible source of uncertainty (Flack et al., 2019). LDs and large wood can clearly alter local morphology, which in turn can alter hydraulic response through feedback cycles of erosion and deposition (Lo et al., 2021). Despite this, those models that solve only for the hydrodynamic component often produce erodibility maps (Hankin et al., 2019; Pearson, 2020) or report the cross-sectional or depth-averaged velocity and shear stress components (Bair et al., 2019) on the bed and banks. However, many previous studies have focused on the reach scale, or small catchments (< 10 km²), simulating one or a small number of LDs (Addy and Wilkinson, 2019) in isolation. It is therefore difficult to validate results at larger scales, especially when combined with a greater range of flows, rarer high flow events, and increased complexity (Metcalf et al., 2017). Those that have attempted catchment-scale simulations, such as the network models of Hankin et al. (2020) and Follett and Hankin (2022), have not considered sediment transport in any of the scenarios explored. A few studies do exist that simulate sediment transport and riverine geomorphic evolution in response to LDs. Walsh et al. (2020) used the landscape evolution model (LEM) CAESAR-Lisflood (Coulthard et al., 2013) to assess the impact on channel response and suspended sediment discharge of large wood in a small headwater catchment. Large wood was represented using the bedrock layer in CAESAR-Lisflood (i.e. an unerodible, fixed bed) but such an approach does not represent

LD function and does not permit the throughflow of water nor represent a lower gap to allow for unimpeded passage of baseflows. Pearson (2020) also used CAESAR-Lisflood to implement runoff attenuation and used an approach that features as edits LDs within the terrain. This method allowed features to be eroded but again lacked porosity and a lower flow gap. As such, no work currently exists that incorporates both the inherent “leakiness” of LDs and the ability to simulate a lower gap coupled with sediment transport to evaluate geomorphic evolution within a numerical model. Here we address this methodological gap to advance substantive understanding.

The aim of this paper is to explore the relative behavioural impact of a simple LD on sediment transport processes and subsequent influences on discharge and water storage through a small reach. To do this, we first introduce new functionality for CAESAR-Lisflood that can represent LDs through the restriction of flow. Second, we evaluate the sensitivity of the model to DEM resolution, and third, we assess the impact of LD roughness and gap size on geomorphology and water storage. Finally, we present the implications of numerically simulating LDs coupled with sediment transport processes to inform future modelling studies.

2 CAESAR-Lisflood

2.1 Model description

Geomorphic processes are complex, and consequently high-fidelity numerical models designed to simulate them are also complex and computationally demanding, meaning long-term simulations (tens to hundreds of years), or multiple simulations of different scenarios, can take substantial computational resources. Time is a barrier to decision-makers who may wish to use information from simulations in order to plan flood management interventions and/or river restoration schemes. LEMs reduce complexity by simplifying processes, increasing computational efficiency and enabling useful and timely information to be extracted. Originally designed to investigate broad-scale controls and behavioural changes to landscapes as they develop over long timescales (10^2 – 10^6 years), LEMs have been key to a range of advances in the understanding of long-term geomorphic processes. Developments in computational power have increased the complexity of some LEMs whilst retaining their efficiency, leading to the development of “second-generation” LEMs such as CAESAR-Lisflood, herein referred to as CL. This has extended the capabilities of the original LEM for wider applications, including, for example, landslide risk (Xie et al., 2022), hazards to electricity transmission towers (Feeney et al., 2022), mining (Hancock et al., 2017), and flood risk management (Croke et al., 2016; Ramirez et al., 2020).

CAESAR-Lisflood is a second-generation LEM that merged the original CAESAR LEM with the 2D hydraulic

code, Lisflood-FP (Bates et al., 2010), replacing the original simplistic steady-state hydraulic code (Coulthard et al., 2013). The development allows the model to simulate geomorphic processes at the event scale whilst retaining its efficiency. Further developments within CL has enabled application in flood risk management through the ability to apply spatially distributed rainfall within the model domain, allowing for representation of convective events (Coulthard and Skinner, 2016). As such, CL is a suitable model to further enhance with new tools to simulate NFM approaches, such as LDs. CL can have one or more direct hydraulic source inputs that can be used in both catchment and reach modes in combination with rainfall. CL requires minimal data (elevation and rainfall or a discharge input) for operation; uses readily available regular gridded DEM data with a range of grid sizes; is open-source and highly customisable; and, crucially, can simulate spatially distributed morphodynamic evolution utilising up to nine grain size fractions (Meadows, 2014; Hancock et al., 2015; Pearson, 2020; Walsh et al., 2020). Fluvial erosion and deposition are governed by three selectable sediment transport laws: Wilcock and Crowe (2003), Einstein (1950), or Meyer-Peter and Müller (1948). As CL ingests a regular raster grid, attributes can be assigned to each unique cell, including roughness (Manning’s n) and TOPMODEL m value (Li et al., 2023). Here, version 1.9j, first released in August 2019, is used as the baseline for development (available at <https://sourceforge.net/projects/caesar-lisflood/files/>, last access: 30 September 2022).

2.2 Leaky dam module

The approach developed herein represents the leakiness of a LD, its water-depth-dependent impact on the water column, and changing efficacy due to implicit geomorphic changes. There are multiple different designs for LDs, from those that are more natural and better emulate natural large wood to those that are more engineered, with slots for water to pass through (Lashford et al., 2022; Quinn et al., 2022). The module presented herein allows for the simulation of gaps below LDs, a common design feature, in a way that can be altered due to erosion or deposition. In addition, the user can specify an install time within the simulation timeline, thus allowing the model to reach a steady state without LDs impacting hydro- or morphodynamics. LDs can then be inserted into evolved landscapes, allowing for a range of experimental simulations that more realistically simulate LD installation.

The LD function uses a dynamic value for Manning’s n roughness (henceforth n) for cells that have been labelled as containing a LD. This method is straightforward to apply within a model domain as specific cells can be identified to place the LD in combination with other roughness variables, such as in-channel or floodplain boundary roughness (Liu et al., 2004; Kitts, 2010; Odoni and Lane, 2010; Dixon et al., 2016; Pinto et al., 2019; Rasche et al., 2019; Barnsley,




Figure 1. Schematic showing hypothetical cross sections for LD-containing cells. Elevations are represented as z_n and heights relative to z_{bed} as h_n . The LD becomes effective once the elevation of the water level (z_{water}) exceeds the elevation of the bottom of the LD (z_{base}). Throughout simulations, the elevations (z_{base} and z_{top}) expressing the absolute top and bottom elevations of the LD do not change, so changes to the elevations of the water level (z_{water}) and the bed level (z_{base}) will change its efficacy.

2022; Senior et al., 2022). Roughness values can be determined from field observations and utilised in numerical models (Shields and Gippel, 1995; Curran and Wohl, 2003; Kitts, 2010; Dixon, 2013), but careful consideration of the application and transferability of roughness values between field sites and at different scales must be considered, especially in steep river channels where higher roughness has less of an impact compared to a physical blockage (Addy and Wilkinson, 2019). There is currently no implementation of a stage-dependent dynamic roughness value for LDs in the literature. This is an important limitation of previous approaches since the relationship between flow resistance and LDs is known to be stage-dependent (Jeffries et al., 2003; Keys et al., 2018; Addy and Wilkinson, 2019; Muhawenimana et al., 2023). Senior et al. (2022) highlight that care must be taken when interpreting the effectiveness of changing roughness values as it can slow the flow of water rather than discretely store it. The approach adopted herein emulates the behaviours often observed by LDs but does not account for the entire hydraulic complexity as observed in laboratory studies (e.g. Muhawenimana et al., 2021).

The function applied herein determines the value of n to be used to estimate flow through each cell containing a LD according to the proportion of the water column behind the LD that is in contact with the LD at each time step. If there is no LD, or the activation criteria are not met, n defaults to the default bed roughness defined by the user, n_{global} . Otherwise, a unique roughness, n_{local} , is calculated for each time step for each LD up to a maximum user-defined value (n_{max}). Adjustment to n is performed as a function of cell properties (see Fig. 1): the initial elevation of the bed (z_{bed}), current bed elevation upstream of the LD (z_{USbed}), and elevation of the upstream water level (z_{water}). In addition, there are three user-defined properties: (1) the size of the vertical gap between the riverbed and the base of the LD on installation, h_{gap} ; (2) the distance between the bed elevation at the start of the simulation and the top of the LD, h_{top} ; and (3) the maximum value of n if the entire water column upstream of the LD is in contact with it, n_{local} .

CL employs a first-order upwind scheme (Coulthard et al., 2013). Therefore, for $cell_{x,y}$, the model calculates elevation values from the cell upwind of the LD, from where water




Figure 2. Leaky dam representation on a regular grid, where 1 denotes an LD. Red shows the potential location for the LD along a cell face; yellow the flow direction between cells; and blue relative water depth, with a darker colour denoting deeper water. The location of the LD changes with flow direction: (b) flow from north to south, therefore the LD is on the northern cell face, (c) flow from east to west; therefore, the LD is on the eastern cell face.

originates, and the LD is assumed to take effect on the face between cells. The hydraulic model within CL uses the four cardinal neighbours (D4) to transport water and sediment; therefore, only connected grid cells can transport material (O’Callaghan and Mark, 1984), resulting in no diagonal connections, as with the D8 flow direction algorithm. As such, for cell properties, the x and y coordinates can vary based on flow direction: $property_x = cell_{xmy}|cell_{x-1,y}$, depending on which has the greatest water level in the x direction, and $property_y = cell_{x,y}|cell_{x,y-1}$ for the y direction.

There are two different methods of assigning a cell as containing a LD. The first method uses codes with a value between 0 and 5 assigned to each cell. If it is 0, there is no LD; if it is greater than 0, the cell is assigned one of five user-determined LD parameters, including a gap size (h_{gap}), height (h_{top}), and maximum roughness. Upon initialisation, the model converts those parameters into z_{base} , z_{top} , and n_{max} . Additionally, the module determines the upstream direction and automatically assigns the LD to the corresponding cell face as shown in Fig. 2. This enables the LD to be placed without considering flow direction.

When the model is initialised, for each time step, the LD module runs through an iterative process, represented by Eq. (1), that determines the proportion of the LD in contact with the water column and calculates the scale of n using a blockage ratio (BR). BR captures increasing LD rough-

ness with increasing stages to reflect increasing complexity as a greater vertical area of the channel is obstructed. Further empirical data are required to assess this assumption. If the LD is overtopped, the blockage ratio reduces because the cross-sectional area of flow increases, while the cross-sectional area of the LD remains constant. Therefore, the relative cross-sectional roughness reduces and thus n is reduced. Equally if the LD is not at maximum capacity, that is, $h_{\text{water}} = h_{\text{top}}$, n is scaled to less than n_{max} accordingly. The global Manning value (n_{global}) is then combined with the scaled n_{max} to create n_{local} as shown in Eq. (2), which is used in subsequent processing steps by CL.

$$\text{BR} = \max\left(\frac{\min(z_{\text{water}}, z_{\text{top}}) - \max(z_{\text{base}}, z_{\text{bed}})}{h_{\text{water}}}, 0\right) \quad (1)$$

$$n_{\text{local}} = n_{\text{global}}(1 - \text{BR}) + n_{\text{max}}\text{BR} \quad (2)$$

The proposed depth-weighted roughness representation method enables the user to emulate real-world implementations of LDs. Roughness (or porosity) quantification for structures such as LDs is often impractical at a large scale due to the required resolution of remotely sensed data as well as the characteristics of the LD itself – geometry, litter cover, sorting, and wood size, for example (Dixon, 2016; Livers et al., 2020). As such, the n method represents a range of values that can be used to assess the extent of flow restriction caused by an LD and its relative impacts.

3 Methods

Prior to evaluating the impact of LDs on the hydro-geomorphology, sensitivity tests were conducted to understand the relationship between DEM grid resolution and the impact of simulating sediment transport compared to only the hydraulic component. Sensitivity analysis was performed using a single rainfall input – a 6 h, 10 % AEP rainfall event – derived from the flood estimation handbook (Stewart et al., 2013) on a synthetic DEM (herein referred to as DEM_T).

3.1 Synthetic reach-scale terrain

The model domain was 160 m long and 100 m wide and represents a second-order stream. The DEM had the same average slope as a prototype site (0.01 m m^{-1} ; Wolstenholme, 2023) where LDs were installed in 2019 and was created by linear interpolation between the high and low survey points in the reach captured with a Topcon OS-103 Total Station (TS). DEM_T was resampled preserving minimum elevations to DEM_{T_j}, where j represents the cell resolution (of either 1, 2, or 4 m as part of the grid sensitivity tests), ensuring channel depth and slope angle were preserved. To assess the influence of DEM resolution on model behaviour, a 1 m deep, 4 m wide channel was burnt into all DEMs.

3.2 Model setup

A nested approach was used to drive model experiments at the reach scale. First, to derive discharge and sediment input for the reach of interest, discharge from the wider upper catchment, DEM_C (2 km^2 ; obtained from OS Terrain 5 data at 5 m resolution; Ordnance Survey, 2020), was modelled using an extract of radar rainfall observations derived from the UK NIMROD radar network record for 2006–2020 (Met Office, 2003). This was applied at a 60 min time step to DEM_C as a global rainfall input to spin up the model and remove initial sediment extremes exported from the system due to an initial condition of homogenous grain size distributions (GSDs) across the DEM. This ensured that the sediment was distributed throughout the catchment in equilibrium with the topography. This was then repeated to derive a hydraulic and sediment discharge input for the reach-scale model.

The input grain size distribution was calculated using field data from Wolstenholme et al. (2024a). The site from which the grain size distribution was collected was approximately 2 km downstream of the LD because LDs had been installed prior to surveying as the channel grain size distribution in the reach of interest would not be representative of a pre-LD scenario. The b (intermediate) axis of > 400 randomly selected clasts were measured from four locations in the reach, and the distributions binned into the nine default classes, as used by CL (see Fig. 3). The grain size distribution was found to have a D_{50} of 12.8 mm, which was applied globally across the modelled reach domain. Within the model, no sediment was transported in suspension, and the Wilcock and Crowe (2003) sediment transport law was selected within CL since it was developed using a mixture of both sand and gravel, which is appropriate for the grain sizes used.

3.3 Experimental design

Each DEM_{T_j} had a single LD installed 100 m downstream of the model input to assess geomorphic effects surrounding the LD and reduce potential impact from the model boundaries. A single rainfall storm was used (0.1 AEP with a 6 h rainfall duration) nested within a 120 h period of baseflow with a 60 s time step. An initial period of 33.3 h was used to fill the river reach and establish a hydraulic equilibrium, followed by the input to the reach model of a catchment-derived storm for a further 50 h and then baseflow for the remainder of the run. The storm input was appended onto the spin-up period to ensure that all experiments that involved sediment transport had identical initial conditions. The LD was “installed” following the spin period, 33 h prior to the onset of the storm used for analysis. This allowed the river channel to adjust to the baseflow without being impacted by the LD. Two LD gap variants were tested in each scenario (0 and 0.2 m), and the maximum roughness (n_{max}) of the dams was set to 0.16 (chosen as a conservative estimate of LD rough-




Figure 3. Grain size distribution used in experiments from Wolstenholme et al. (2024a).

ness after Curran and Wohl, 2003; Dixon et al., 2016; Addy and Wilkinson, 2019).

LD height and width was constant throughout the experiments (0.5 m above initial channel bed and 4 m wide). Output data from the simulations, which provided information on outlet discharge, sediment yield for each grain size and total sediment yield, were recorded at a 1 min time step. All tests were repeated with CLs “flow-only” option. When on, the erosion and deposition modules of the model are bypassed, and it functions as a 2D hydraulic model with a rigid boundary as such hydraulic simulations were started 30 d prior to the onset of the storm. To assess the impact of the LDs on the system, the differences in peak discharge and storage capacity over time were calculated, comparing the cumulative discharge for a given storm to a corresponding “no LD” baseline scenario. Finally, the influence of changing LD roughness and gap size was assessed.

4 Results

4.1 Computational expense

Figure 4 shows the number of iterations required to complete the simulations for the performed experiments. Iterations are a useful proxy for model efficiency, independent of the computer used to perform the simulations. They show that for a decreasing grid resolution, fewer iterations are required across all experiments. Simulation of the LD with only the hydraulic model enabled results in little increase in computational expense (averaged standard deviation = 20 259), whereas enabling sediment transport drastically increased




Figure 4. Computational expense represented as the number of model iterations for simulations with, and without, LDs.

model iterations often by over 200 % across all DEM resolutions.

4.2 Model domain outputs

The influence of the LD on the model domain outputs was assessed through comparing the baseline (no LD scenario) to each of the LD variation experiments after the spin period, measured from the outlet of the model. Hydraulic-only simulations were more stable than the sediment-transport-enabled counterparts, as shown in Fig. 5. When $h_{\text{gap}} = 0$, hydraulic-only experiments show discharge attenuation of up to 1 % when the LD is installed and further attenuation of up to 2.4 % on the rising limb of the storm before increasing ΔQ (the change in Q between simulations) to 3.1 % during the peak. When $h_{\text{gap}} = 0.2$, instantaneous discharge attenuation is not seen when the LD is installed, but the LD does increase discharge on the rising limb and the peak by up to 3 %, before attenuating Q on the falling limb for both higher DEM resolutions, but reduces flows when a 1 m grid cell size is used (Fig. 5).

In contrast, when sediment transport was enabled, ΔQ was more variable after the storm. There was instant attenuation of up to 50 % when $h_{\text{gap}} = 0$, for DEM_{T2} and DEM_{T4}, and also up to 50 % attenuation during the storm (see Fig. 5c). In contrast, when $h_{\text{gap}} = 0.2$, there was no reduction in Q upon LD installation, as seen in the equivalent hydraulic-only scenario, and a reduction in Q of up to 4.7 % for the 4 m DEM during the rising limb. For all sediment-transport-enabled experiments, the falling limb of the storm and remainder of the simulation time shows up to ± 25 % deviation from the baseline scenario due to Q go-




Figure 5. Impact of DEM grid resolution on predicted Q for sediment-transport-disabled/enabled experiments with the LD gap size set to 0 m (a, c) or 0.2 m (b, d). The black line denotes input discharge (right axis, uniform across all experiments).

ing out of phase with the baseline. DEM_{T1} had an overall reduction in Q (maximum = -10%) following the peak of the storm compared to coarser grid resolutions DEM_{T2} and DEM_{T4} that increased Q (maximum $+12\%$ and $+25\%$, respectively). Where $h_{\text{gap}} = 0.2$, although the influence of the LD had little impact on the peak, there was much larger disruption to the discharge on the falling limb. These disruptions represent a deviation in Q of up to $0.014 \text{ m}^3 \text{ s}^{-1}$ as a result of sediment transport and the presence of the LD.

The impact on Q_s (sediment discharge) was determined using the same approach for Q detailed previously but by comparing the cumulative Q_s rather than instantaneous discharge. When the LD was installed, there was no impact on Q_s efflux of the model domain for any experiment. Across all the grid resolutions used, ΔQ_s was found to increase immediately following the peak of the storm, and sediment was lost from the system. The 4 m grid resolution had a substantially larger sediment efflux (see Fig. 6) when $h_{\text{gap}} = 0$ and to a lesser degree where $h_{\text{gap}} = 0.2$. On the falling limb and remainder of the simulation, the 1 and 2 m DEM resolutions had negative $\Delta \Sigma Q_s$, indicating that sediment efflux was lower than that of the baseline scenario and that sediment was stored in the reach. Although the 4 m resolution showed a similar behaviour, sediment efflux was continuously greater than the baseline.

4.3 Geomorphological evolution

Geomorphological evolution was assessed within the model domain by comparing the average channel width elevation change to the baseline scenario for all experiments shown in Fig. 7. Installing a single LD substantially influences bed elevation change throughout the system. All simulations regardless of grid resolution follow the same pattern of elevation change. There was increased deposition 60–100 m downstream (average $+0.12 \text{ m}$, maximum $+0.25 \text{ m}$). The cell immediately upstream of the LD was typically erosive for DEM_{T4} when $h_{\text{gap}} = 0$ and 0.2 (0.07 and 0.11 m , respectively). When the channel width was greater than one cell (i.e. DEM_{T1} and DEM_{T2}), there was also deposition predicted in the upstream cell of up to 0.12 m . Typically, when $h_{\text{gap}} = 0.2$, there was less bed erosion predicted.

Immediately downstream of the LD had the most substantial bed elevation change, with all scenarios being highly erosive from -0.08 m (DEM_{T1}; $h_{\text{gap}} = 0.2$) to -0.99 m (DEM_{T4}; $h_{\text{gap}} = 0$). When $h_{\text{gap}} = 0$, there was more erosion in the downstream cell than when $h_{\text{gap}} = 0.2$. Downstream of the LD, a depositional zone was predicted, with an elevation change similar in magnitude to the eroded cell upstream, ranging from 0.2 – 0.85 m (DEM_{T1}; $h_{\text{gap}} = 0.2$ and DEM_{T4}; $h_{\text{gap}} = 0$, respectively), and thus similarly, there was more deposition where $h_{\text{gap}} = 0$. Overall, the order of magnitude




Figure 6. Cumulative sediment discharge ($\Sigma\Delta Q_s$) for the 0m LD gap (a) and 0.2m gap (b) experiments. Input discharge shown for reference.




Figure 7. Relative average channel width bed elevation change for sediment-transport-enabled experiments. Bars show individual cell elevation change compared to the baseline scenario, with the mean represented as a point for DEM_{T1} and DEM_{T2}.

and directionality of the elevation change are similar across all scenarios. Finally, for all scenarios following the second cell most downstream of the LD, there was fluctuating propagation of bed elevation change predicted of the order of ± 0.10 m until the edge of the model domain.

4.4 Leaky dam parameter adjustment

To explore the impact of varying n values and the LD gap to build an envelope of potential responses, DEM_{T2} was chosen to use the highest-resolution DEM that is practical to run across a suite of scenarios whilst retaining a reasonable representation of the initial topography. Grain size, rainfall input, and LD location were kept constant. Using the same hydraulic input as above, a no-LD baseline experiment was performed in addition to a matrix of 25 tests varying two

LD parameters. First, the maximum LD roughness (n_{max}) was varied between 0.12 and $0.20 s m^{-1/3}$ at intervals of $0.02 s m^{-1/3}$. Values herein are based on empirical studies and are representative of naturally occurring log jams (Curran and Wohl, 2003; Dixon et al., 2016; Addy and Wilkinson, 2019). Second, the LD gap size was systematically varied from 0 – 0.4 at 0.1 m intervals. Hydraulic and sediment-transport-enabled simulations were both performed, resulting in a total of 52 experiments.

4.4.1 Water storage

Sediment-transport-enabled simulations showed water storage at least an order of magnitude greater than the hydraulic equivalent. Where there was no LD gap, water was instantly stored upon LD installation until the onset of the storm,




Figure 8. Water storage ($\Delta\Sigma Q$) for hydraulic and sediment-transport-enabled simulations, separated by the LD gap size in metres (0.3 and 0.4 m gap simulations were omitted due to their having no impact). Manning’s n ($\text{s m}^{-1/3}$) denoted in legend, with input discharge represented in red. Note different y-axis scale.

where rougher LDs were found to store the greatest volume of water. Larger gap sizes did not store water upon LD installation, rather when stage reached the base of the LD. Where the gap size was 0.3 m or greater, there was no difference in water storage, and therefore the LD did not engage with the river. For all remaining scenarios, water storage was the greatest during the peak of the storm, with increasing gap size resulting in diminished storage during the peak for both hydraulic and sediment simulations. There was no subsequent water storage for hydraulic simulations except where there was a 0 m gap. In contrast, when simulating sediment transport, the system stored 0.95–2.2 m³ of water when compared to the baseline experiment, as shown in Fig. 8, with diminishing effectiveness when gap size was increased.

4.4.2 Sediment transport

Sediment transport was found not to be influenced by the installation of the LD at 20 h, regardless of gap size; however, only when the gap was 0.2 m or less did the LD influence Q_s during the storm (see Fig. 9). Prior to the peak of the storm,

Q_s was reduced by $> 0.03 \text{ m}^3$ when the LD engaged with the flow compared to the baseline scenario (see Fig. 9a–c), but there was little variability prior to the peak (average standard deviation of 0.008). Following the peak of the storm, the influence of roughness variability was more pronounced with an increase in Q_s ($\Sigma\Delta Q_s$ of 0.25–0.8 m³); however, there was no clear trend between the volume of sediment exiting the model domain (Fig. 9) and the chosen roughness value. However, increasing LD gap size did result in less sediment being lost out of the domain, likely due to there being a lower energy gradient induced by the LD. Following the storm, sediment discharge was lower than the baseline scenario (except where n is 0.14 or 0.18 $\text{s m}^{-1/3}$ and there is no LD gap) with a maximum difference of 0.5 m³ (where n is 0.16 and the LD gap is 0.2 m).

4.4.3 Elevation change

In Sect. 4.3, it is shown that the LD mainly impacted the elevation of cells immediately upstream and downstream of the LD. As such, only these three sections of the channel




Figure 9. Cumulative sediment yield difference compared to the baseline scenario for 0, 0.1, and 0.2 m gap sizes (a–c, respectively) separated by Manning’s n ($\text{s m}^{-1/3}$). Input discharge shown by red curve. In the figure, 0.3 and 0.4 m gap simulations were omitted due to their having no impact.

were considered for localised bed elevation change analysis, as shown in Fig. 10. When the LD gap was 0.3 m or greater, there was no influence on bed morphology. Immediately upstream of the LD (Fig. 10a), bed erosion magnitudes of 0.05–0.14 m were simulated, with a 0 m gap and high-roughness ($0.18\text{--}0.2 \text{ s m}^{-1/3}$) LD conditions, with lower volumes of erosion simulated alongside larger gap sizes and lower roughness values. There was a non-linear relationship between these parameters, with erosion magnitudes decreasing rapidly for higher roughness values as gap size increases, yet not as rapidly with lower roughness values applied. For example, where the LD gap is 0.1 m, erosion magnitudes are more closely clustered (0.105–0.092 m) than for other gap sizes. Zones immediately downstream of the LD (Fig. 10b) experienced the most erosion, with up to 0.85 m of scour. The patterns and relative levels of bed erosion closely match that of the zones immediately upstream of the LD, however, at greater orders of magnitude. Finally for the second cell downstream (i.e. 4 m from the LD), there is only deposition that is predicted (0.35–0.57 m). Higher roughness values experienced greater levels of deposition, which also decreased with increasing gap size.

5 Discussion

5.1 The CAESAR-Lisflood model

The results presented above demonstrates how CL can effectively represent LDs by dynamically adjusting localised Manning’s n roughness values whilst accounting for different LD heights and gap sizes as a function of the proportion of the water column upstream of the LD. Placement of LDs is straightforward and can be achieved using a geographic information system or through the creation of a regular grid file, and simulations can be achieved using minimal data – a DEM, hydraulic input, and sediment GSD – to produce an overview of how a reach responds to LD installation. CL could therefore be used to explore the relative influence of LDs and their parameters throughout a given reach to indicate a behavioural response, such as increased flow attenuation or enhanced geomorphic diversity following calibration. Through developing the ability to install a LD after a river channel has evolved to baseflow conditions, the simulation, and its output, are less affected by the bias of having these structures installed from the start of the simulation. As such, LDs are generated after baseflow has been established, which is more representative of the real LD installation pro-




Figure 10. Elevation change for the cell immediately upstream of the LD (a), immediately downstream (b), and 4 m downstream (c) separated by Manning's n ($\text{s m}^{-1/3}$). In the figure, 0.3 and 0.4 m gap simulations were omitted due to their having no impact.

cess, where wood is often felled and then anchored in situ while the river is flowing (Grabowski et al., 2019; Lo et al., 2021).

The effect of LDs – as well as natural log jams – is known to be stage-dependent (Jeffries et al., 2003; Keys et al., 2018; Addy and Wilkinson, 2019; Muhawenimana et al., 2023); therefore, it is important to ensure that the model can account for Manning's n being variable. Development of the LD module introduced above in CL builds upon previous work outlined by others (Dixon et al., 2016; Addy and Wilkinson, 2019; Hankin et al., 2020; Pearson, 2020; Walsh et al., 2020; Hill et al., 2023), filling a research gap through provision of a tool capable of generating dynamic roughness values that ensure that temporal variability in the stage-dependent LD–water relationship is captured. In addition, as CL utilises a regular raster grid, the required resolution can be adapted based on user requirements as well as computational resource availability. CL is a reduced complexity LEM that is not designed to simulate complex high-resolution channel flows but rather larger reach- and catchment-scale change over longer durations. As CL has the capability to simulate high-resolution environments (both spatially and temporally) at an increased computational expense, it is important to recognise the impact of cell size throughout simulations. However it is also important to note that in the simulations presented above the order of magnitude of predicted change was similar, regardless of model cell size, for water storage, geomorphology, and discharge.

High-resolution cell sizes are the most computationally expensive. Increasing spatial resolution from two metres to one metre results in a 4-fold increase in the number of cells that occupy the same extent, with almost double the number of model iterations. The increase in iterations is also dependent on the area that water interacts with and the impact the water has on those cells. When simulating the impact of LDs and sediment transport, there was a 2-fold increase in the number of iterations compared to a no-LD scenario

at all resolutions tested. In addition, higher-resolution cell sizes (such as 2 m) without LDs performed a similar number of iterations to the 5 m resolution experiments with LDs when simulating sediment transport. As such, scale has substantial consequences for future work when simulating large catchments despite having minimal influence on discharge. Increasing cell size results in a decrease in the accuracy of the true topography as the landscape is smoothed (Schoorl et al., 2000; Claessens et al., 2005); therefore, it is important to utilise as high a resolution of the grid as practical without compromising the quality of model outputs. Resampling the input DEM can lead to variable channel widths and therefore a vast difference in potential water storage, which can introduce a substantial bias into the results if not considered. Due to this, CL should only be used to understand broad behaviours that might be representative of a reach or catchment to discern information of interest where a finer resolution is impractical, especially at larger scales.

Cell size also has an impact on predicted geomorphic evolution. Higher resolutions can capture smaller-scale fluctuations in bed elevation. Nevertheless, herein it is found that coarser resolutions are able to predict relative changes that were of similar magnitudes to those predicted for finer-resolution grids. All simulations predicted scour immediately downstream of the LD followed by a zone of deposition, with the perturbation fluctuating in magnitude as the signal weakens distal to the LD. Skinner and Coulthard (2023) showed that in CL, as the DEM grid cell increases, the representation of the hydrological network can become degraded, and although the model recorded similar total sediment yields following a 30-year continuous time series over a 0.5 km^2 catchment, this was from fewer geomorphologically active events. In this study, a single-thread linear channel is used to evaluate the behaviour of the LD without introducing more complex morphological change or alterations to flow characteristics similarly to a laboratory environment. As such, the findings of Skinner and Coulthard (2023) regarding connec-

tivity do not apply here; however, further testing is required to evaluate the impact of a longer time series on geomorphic evolution and LD efficacy.

LEMs are notorious for being difficult to validate due to the lack of availability and paucity of calibration data (Wong et al., 2021). Combined with many adjustable parameters and initial conditions, there is a high probability for model equifinality (Coulthard and Skinner, 2016; Hancock et al., 2016; Skinner et al., 2018; Skinner et al., 2020). It is, however, possible to treat the outputs from an LEM, such as CL, in more abstract perspectives and use the results to identify the influence of intrinsic variables and the addition of structures to a system. As such, care must be taken when extracting and interpreting data outputs and using appropriate metrics in order to capitalise on data produced (Skinner et al., 2018). When simulating sediment transport and recording the output with high temporal resolution, discharge contained sharp increases and decreases due to pulses of sediment being suddenly mobilised within the system when the transport threshold was reached (as seen in Fig. 5). Thus, water storage is perhaps a more useful mechanism for accessing the influence of LDs at this scale, especially without producing vast amounts of extra data. A direct comparison can be performed between simulations which indicate the total volume of water being stored in a system compared to a system without LDs installed. The same practice can be applied to sediment stored within the system and aligned with the output hydrograph.

5.2 Sensitivity considerations

For the simple reach DEM_T used in the sensitivity suite of experiments, it is clear that finer-resolution grids are more computationally expensive due to the number of cells to be processed, yet the LD module almost doubles this computational expense. Despite this, elevation change across the river profile follows a similar pattern regardless of grid resolution and also has the same order of magnitude and directionality of change as shown in Fig. 7. Grid resolution when simulating LDs impacts both Q and Q_s through increasing the effectiveness of Q reduction for both hydraulic and sediment-transport-enabled experiments. The activation of the LD also varied by up to 40 min depending on grid resolution. When simulating sediment transport, Q is substantially noisier than hydraulic-only simulations, most likely due to CL reaching the threshold required to transport sediment. The noise in the data must also be considered when analysing simulation outputs; however, this may also be a function of the high temporal resolution output recording. Averaging sediment transport data to a lower temporal resolution (e.g. hourly) results in smoother outputs at the cost of temporal detail. An alternative measure, water storage, calculated as the difference between cumulative Q for both the baseline and the LD implementation simulations, may provide additional clarity on the broad impact of LD interventions. Additionally, Q_s and sed-

iment storage are drastically different when increasing grid resolution from 2 to 4 m, resulting in a 5-fold increase in sediment discharge.

Care must be taken when using the LD module for CL as the right results, such as elevation change and Q reduction, may be overestimated when using coarser grid resolutions. The scenarios simulated herein align well with the relative influence of LD from both field and laboratory observations, including the formation of downstream pools (Lo et al., 2021, 2022; Muhawenimana et al., 2023), and the potential for sediment storage upstream (Comiti et al., 2008). Future work should focus on calibrating and developing this tool as a flexible and rapidly deployable option for LD simulations in CL that should currently be used heuristically to mitigate the need for calibration. The LD module for CL can therefore be best used to understand the relative impact of LDs in larger, complex catchment to identify their individual impact on FRM.

5.3 Implications

Typically, for FRM, interventions are designed to reduce the risk of a specific flood event threshold derived from historic empirical data within a catchment. The effectiveness of an FRM structure in reducing the impacts of a given AEP is established through rigorous hydraulic modelling of different dimensions of the flow and structure; however, modelling must be proportionate to the project considered (Environment Agency, 2022). The results herein show that understanding the influence of an FRM intervention on sediment transport is vital as geomorphic forcing resulting from a structure enables the estimation of the efficacy of an intervention for a catchment. Sediment transport becomes increasingly important when unintended geomorphic adjustment to “hard-engineered” structures reduces the efficacy of structures, potentially increasing flooding downstream (Hesselink et al., 2003; Pinter et al., 2006; Hudson et al., 2008; Benito and Hudson, 2010). Utilising an understanding of both historic and present geomorphic changes to structures enables geomorphologists to inform FRM strategies (Arnaud-Fassetta et al., 2009). Indeed, without understanding the geomorphic consequences, flood mitigation interventions have the potential to do more harm than good.

Channel evolution alongside LD interventions must be considered for both single storm events and long-term simulations due to the observations identified above. A LD fixed in situ can have a substantial effect on the hydrological regime as well as the broader geomorphology of the river channel, which can, in turn, influence outcomes of flood risk modelling. Often, numerical modellers omit the geomorphological process – especially at the event scale – for increased computational efficiency as they are considered not to have an impact greater than that of the uncertainties already present within the model (Flack et al., 2019), yet im-

pounding a channel with a LD can cause substantial geomorphological evolution from a single event alone.

It has been shown that modelling sediment transport can have an impact on the total volume of water that a reach is able to store compared to modelling hydraulics alone. It is important to therefore consider how modelling these processes can further inform future work, such as placement of LD interventions throughout a catchment, as well as how best to utilise these resources to effectively identify locations for river restoration projects. Additionally, numerical modellers can utilise the LD module in CL from minute, event, annual, decadal, and greater scales if desired, customising the outputs to the users' needs. CL has the capability to save an elevation file (amongst many others) at a given time step, furthering the understanding of how these structures evolve throughout a storm or rainfall sequence. Additionally, other types of structures with porosity can be evaluated with the model if it can be defined through its height, gap (or lack thereof) and roughness – for example, natural wood, bridges, and bunds – and presents opportunities for further study.

The results herein suggest that practitioners should carefully consider the LD gap size as well as roughness of the intervention when installing the structure. Results here show that there is little impact on peak discharge for a single LD in a linear system; however, the LDs used here are not designed to engage with the floodplain, and it is therefore not utilised. Larger gap sizes activate later in the storm and therefore may be used as a flood delay system to only capture high flows above a certain height, with careful understanding of flow conditions where the LD is installed. Furthermore, adding more roughness elements to the LD increased potential water storage. The CL tool here uses roughness on a relative scale to provide insight into the impact of a rougher and less rough structure. Roughness can be combined with gap size to produce a similar effect; for example, for DEM_{T2} , a $h_{\text{gap}} = 0.1$ and where $n_{\text{max}} = 0.14$ had a comparable and similar impact to conditions where $h_{\text{gap}} = 0.2$ and $n_{\text{max}} = 0.2$ on downstream deposition. The implementation of dynamic roughness also advances simple LD representation in numerical models, particularly when exploring multi-LD reach and catchment-scale scenarios.

Natural flood management practitioners could also utilise the CL NFM tool to provide an understanding of how installing a given number of LDs may impact their reach and/or catchment of interest to develop a “big picture” overview of their effectiveness for their given application, such as sediment management, flood risk reduction, or habitat development. Numerical modelling should be used in conjunction with field studies to evaluate the potential effectiveness and cost–benefit analysis of the installation of multiple NFM interventions, such as LDs. By enabling researchers and practitioners to easily implement LDs into CL, upper and lower boundaries of the potential impact of installations could be calculated and integrated into different climate scenarios if required. CL presents an opportunity to achieve this with

minimal data requirements so long as the user understands that the output should be regarded as a tool to investigate behaviour of the system and not forecasting the definite impact of LDs or other NFM interventions on a river system.

6 Conclusions

This study incorporated leaky wooden dams (LDs) into a numerical model capable of simulating both the hydrology and the sediment transport efficiently at the reach scale. The model also has scope to expand to the catchment scale whilst simulating multiple complex storm events. The approach used herein has shown that it is important to consider sediment transport and morphological evolution when numerically modelling leaky dams, even at the event scale. This is because of the impacts this has on altering the total volume of water stored by the LDs, in addition to inducing greater geomorphological complexity. Based on a synthetic DEM, LD gap size was shown to be much more important than dam roughness when numerically modelling with the CL method and could be utilised in the future by NFM practitioners looking to install similar structures within a reach and/or catchment. The study also highlights the need to correctly represent a gap in LD models as well as the need to consider adopting a behavioural approach to the numerical modelling of such structures.

Code and data availability. The current version of CAESAR-Lisflood is available from Coulthard et al. (2022; <https://sourceforge.net/projects/caesar-lisflood/>) under the GNU General Public Licence version 3.0 (GPLv3).

The exact version of the model used to produce the results used in this paper is archived on Zenodo and available at <https://doi.org/10.5281/zenodo.12795495> (Wolstenholme et al., 2024b), as are input data and scripts to run the model for simulations presented in this paper.

Author contributions. JW and CS conceived the study and designed the experiments. CS added the LD module into CAESAR-Lisflood code base. JW performed the simulations, data analysis, and writing of the first draft. JW, CS, DM, RT, and DP equally contributed to discussing and interpreting the results and finalising the draft.

Competing interests. The contact author has declared that none of the authors has any competing interests.

Disclaimer. Publisher's note: Copernicus Publications remains neutral with regard to jurisdictional claims made in the text, published maps, institutional affiliations, or any other geographical representation in this paper. While Copernicus Publications makes every effort to include appropriate place names, the final responsibility lies with the authors.

Acknowledgements. This work was performed with support of a studentship awarded to Joshua M. Wolstenholme by the University of Hull.

Review statement. This paper was edited by Andy Wickert and reviewed by Paul Quinn and two anonymous referees.

References

- Abbe, T. B. and Montgomery, D. R.: Large wood debris jams, channel hydraulics and habitat formation in large rivers, *Regul. Rivers: Res. Manage.*, 12, 201–221, [https://doi.org/10.1002/\(SICI\)1099-1646\(199603\)12:2/3<201::AID-RRR390>3.3.CO;2-1](https://doi.org/10.1002/(SICI)1099-1646(199603)12:2/3<201::AID-RRR390>3.3.CO;2-1), 1996.
- Abbe, T., Hrachovec, M., and Winter, S.: Engineered Log Jams: Recent Developments in Their Design and Placement, with examples from the Pacific Northwest, U.S.A, in: *Reference Module in Earth Systems and Environmental Sciences*, Elsevier, <https://doi.org/10.1016/b978-0-12-409548-9.11031-0>, 2018.
- Addy, S. and Wilkinson, M. E.: An assessment of engineered log jam structures in response to a flood event in an upland gravel-bed river, *Earth Surf. Proc. Land.*, 4112, 1658–1670, <https://doi.org/10.1002/esp.3936>, 2016.
- Addy, S. and Wilkinson, M. E.: Representing natural and artificial in-channel large wood in numerical hydraulic and hydrological models, *WIREs Water*, 6, 1–20, <https://doi.org/10.1002/wat2.1389>, 2019.
- Al-Zawaidah, H., Ravazzolo, D., and Friedrich, H.: Local geomorphic effects in the presence of accumulations of different densities, *Geomorphology*, 389, 107838, <https://doi.org/10.1016/j.geomorph.2021.107838>, 2021.
- Arnaud-Fassetta, G., Astrade, L., Bardou, É., Corbonnois, J., Delahaye, D., Fort, M., Gautier, E., Jacob, N., Peiry, J.-L., Piégay, H., and Penven, M.-J.: Fluvial geomorphology and flood-risk management, *Géomorphologie*, 152, 109–128, <https://doi.org/10.4000/geomorphologie.7554>, 2009.
- Bair, R. T., Segura, C., and Lorion, C. M.: Quantifying the restoration success of wood introductions to increase coho salmon winter habitat, *Earth Surf. Dynam.*, 7, 841–857, <https://doi.org/10.5194/esurf-7-841-2019>, 2019.
- Barnsley, I.: Quantifying the benefits of natural flood management methods in groundwater-dominated river systems, PhD thesis, University of Southampton, 219 pp., <http://eprints.soton.ac.uk/id/eprint/468626> (last access: 1 May 2024), 2022.
- Bates, P. D., Horritt, M. S., and Fewtrell, T. J.: A simple inertial formulation of the shallow water equations for efficient two-dimensional flood inundation modelling, *J. Hydrol.*, 387, 33–45, <https://doi.org/10.1016/j.jhydrol.2010.03.027>, 2010.
- Benito, G. and Hudson, P. F.: Flood hazards: The context of fluvial geomorphology, in: *Geomorphological Hazards and Disaster Prevention*, edited by: Irasema, A.-A. and Goudie, A. S., Cambridge University Press, 111–128, <https://doi.org/10.1017/CBO9780511807527.010>, 2010.
- Burgess-Gamble, L., Ngai, R., Wilkinson, M., Nisbet, T., Pontee, N., Harvey, R., Kipling, K., Addy, S., Rose, S., Maslen, S., Jay, H., Nicholson, A., Page, T., Jonczyk, J., and Quinn, P.: Working with Natural Processes – Evidence Directory SC150005, Environment Agency, <https://www.gov.uk/government/organisations/environment-agency/about/research> (last access: 1 May 2024), 2017.
- Cashman, M. J., Wharton, G., Harvey, G. L., Naura, M., and Bryden, A.: Trends in the use of large wood in UK river restoration projects: insights from the National River Restoration Inventory, *Water Environ. J.*, 33, 318–328, <https://doi.org/10.1111/wej.12407>, 2018.
- Claessens, L., Heuvelink, G. B. M., Schoorl, J. M., and Veldkamp, A.: DEM resolution effects on shallow landslide hazard and soil redistribution modelling, *Earth Surf. Proc. Land.*, 304, 461–477, <https://doi.org/10.1002/esp.1155>, 2005.
- Comiti, F., Andreoli, A., Mao, L., and Lenzi, M. A.: Wood storage in three mountain streams of the Southern Andes and its hydro-morphological effects, *Earth Surf. Proc. Land.*, 33, 244–262, <https://doi.org/10.1002/esp.1541>, 2008.
- Coulthard, T. J. and Skinner, C. J.: The sensitivity of landscape evolution models to spatial and temporal rainfall resolution, *Earth Surf. Dynam.*, 43, 757–771, <https://doi.org/10.5194/esurf-4-757-2016>, 2016.
- Coulthard, T. J., Neal, J. C., Bates, P. D., Ramirez, J., de Almeida, G. A. M., and Hancock, G. R.: Integrating the LISFLOOD-FP 2D hydrodynamic model with the CAESAR model: Implications for modelling landscape evolution, *Earth Surf. Proc. Land.* 3815, 1897–1906, <https://doi.org/10.1002/esp.3478>, 2013.
- Coulthard, T. J., Neal, J. C., Bates, P. D., Ramirez, J., de Almeida, G. A., and Hancock, G. R.: CAESAR Lisflood Download-1.9j, Sourceforge [code], <https://sourceforge.net/projects/caesar-lisflood/> (last access: 30 September 2022), 2022.
- Croke, J., Fryirs, K., and Thompson, C.: Defining the floodplain in hydrologically-variable settings: implications for flood risk management, *Earth Surf. Proc. Land.*, 4114, 2153–2164, <https://doi.org/10.1002/esp.4014>, 2016.
- Curran, J. H. and Wohl, E. E.: Large woody debris and flow resistance in step-pool channels, Cascade Range, Washington, *Geomorphology*, 511, 141–157, [https://doi.org/10.1016/S0169-555X\(02\)00333-1](https://doi.org/10.1016/S0169-555X(02)00333-1), 2003.
- Dadson, S. J., Hall, J. W., Murgatroyd, A., Acreman, M., Bates, P., Beven, K., Heathwaite, L., Holden, J., Holman, I. P., Lane, S. N., O’Connell, E., Penning-Rowsell, E., Reynard, N., Sear, D., Thorne, C., Wilby, R., Connell, E. O., Reynard, N., and Sear, D.: A restatement of the natural science evidence concerning flood management in the UK, *P. Roy. Soc.*, 473, 20160706, <https://doi.org/10.1098/rspa.2016.0706>, 2017.
- Deane, A., Norrey, J., Coulthard, E., McKendry, D. C., and Dean, A. P.: Riverine large woody debris introduced for natural flood management leads to rapid improvement in aquatic macroinvertebrate diversity, *Ecol. Eng.*, 163, 106197, <https://doi.org/10.1016/j.ecoleng.2021.106197>, 2021.
- Dixon, S. J.: Investigating the effects of large wood and forest management on flood risk and flood hydrology, ResearchGate, <https://doi.org/10.13140/RG.2.1.4923.2485>, 2013.
- Dixon, S. J.: A dimensionless statistical analysis of log-jam form and process, *Ecology*, 96, 1117–1129, <https://doi.org/10.1002/eco.1710>, 2016.
- Dixon, S. J., Sear, D. A., Odoni, N. A., Sykes, T., and Lane, S. N.: The effects of river restoration on catchment scale flood risk

- and flood hydrology, *Earth Surf. Proc. Land.*, 417, 997–1008, <https://doi.org/10.1002/esp.3919>, 2016.
- Einstein, H. A.: The Bed-Load Function for Sediment Transportation in Open Channel Flows, Technical Bulletin No. 1026, US Department of Agriculture, 1–31, <https://www.vliz.be/imisdocs/publications/75/247675.pdf> (last access: 1 May 2024), 1950.
- Environment Agency: Flood and coastal erosion risk management appraisal: Technical guidance, <https://www.gov.uk/government/publications/fcerm-appraisal-technical-guidance> (last access: 1 May 2024), 2022.
- Feeney, C. J., Godfrey, S., Cooper, J. R., Plater, A. J., and Dodds, D.: Forecasting riverine erosion hazards to electricity transmission towers under increasing flow magnitudes, *Clim. Risk Manage.*, 36, 100439, <https://doi.org/10.1016/j.crm.2022.100439>, 2022.
- Flack, D. L. A., Skinner, C. J., Hawkness-Smith, L., O'Donnell, G., Thompson, R. J., Waller, J. A., Chen, A. S., Moloney, J., Largeron, C., Xia, X., Blenkinsop, S., Champion, A. J., Perks, M. T., Quinn, N., and Speight, L. J.: Recommendations for Improving Integration in National End-to-End Flood Forecasting Systems: An Overview of the FFIR Flooding From Intense Rainfall Programme, *Water*, 114, 725, <https://doi.org/10.3390/w11040725>, 2019.
- Follett, E. and Hankin, B.: Investigation of effect of logjam series for varying channel and barrier physical properties using a sparse input data 1D network model, *Environ. Model. Softw.*, 158, 105543, <https://doi.org/10.1016/j.envsoft.2022.105543>, 2022.
- Galia, T., Poledniková, Z., and Škarpich, V.: Impact of large wood on sediment (dis)connectivity in a meandering river, *Geomorphology*, 453, 109153, <https://doi.org/10.1016/j.geomorph.2024.109153>, 2024.
- Geertsema, T. J., Torfs, P. J. J. F., Eekhout, J. P. C., Teuling, A. J., and Hoitink, A. J. F.: Wood-induced backwater effects in lowland streams, *River Res. Appl.*, 36, 1171–1182, <https://doi.org/10.1002/rra.3611>, 2020.
- Grabowski, R. C., Gurnell, A. M., Burgess-Gamble, L., England, J., Holland, D., Klaar, M. J., Morrissey, I., Uttley, C., and Wharton, G.: The current state of the use of large wood in river restoration and management, *Water Environ. J.*, 33, 366–377, <https://doi.org/10.1111/wej.12465>, 2019.
- Gregory, K. J., Gurnell, A. M., and Hill, C. T.: The permanence of debris dams related to river channel processes, *Hydrolog. Sci. J.*, 303, 371–381, <https://doi.org/10.1080/02626668509491000>, 1985.
- Gurnell, A., England, J., and Burgess-Gamble, L.: Trees and wood: working with natural river processes, *Water Environ. J.*, 33, 342–352, <https://doi.org/10.1111/wej.12426>, 2018.
- Hancock, G. R., Lowry, J. B. C., and Coulthard, T. J.: Catchment reconstruction – erosional stability at millennial time scales using landscape evolution models, *Geomorphology*, 231, 15–27, <https://doi.org/10.1016/j.geomorph.2014.10.034>, 2015.
- Hancock, G. R., Lowry, J. B. C., and Coulthard, T. J.: Long-term landscape trajectory – Can we make predictions about landscape form and function for post-mining landforms?, *Geomorphology*, 266, 121–132, <https://doi.org/10.1016/j.geomorph.2016.05.014>, 2016.
- Hancock, G. R., Verdon-Kidd, D., and Lowry, J. B. C.: Sediment output from a post-mining catchment – Centennial impacts using stochastically generated rainfall, *J. Hydrol.*, 544, 180–194, <https://doi.org/10.1016/j.jhydrol.2016.11.027>, 2017.
- Hankin, B., Metcalfe, P., Beven, K., and Chappell, N. A.: Integration of hillslope hydrology and 2D hydraulic modelling for natural flood management, *Hydrol. Res.*, 506, 1535–1548, <https://doi.org/10.2166/nh.2019.150>, 2019.
- Hankin, B., Hewitt, I., Sander, G., Danieli, F., Formetta, G., Kamilova, A., Kretzschmar, A., Kiradjiev, K., Wong, C., Pegler, S., and Lamb, R.: A risk-based network analysis of distributed in-stream leaky barriers for flood risk management, *Nat. Hazards Earth Syst. Sci.*, 20, 2567–2584, <https://doi.org/10.5194/nhess-20-2567-2020>, 2020.
- Hesselink, A. W., Weerts, H. J. T., and Berendsen, H. J. A.: Alluvial architecture of the human-influenced river Rhine, The Netherlands, *Sediment. Geol.*, 161, 229–248, [https://doi.org/10.1016/S0037-0738\(03\)00116-7](https://doi.org/10.1016/S0037-0738(03)00116-7), 2003.
- Hill, B., Liang, Q., Boshier, L., Chen, H., and Nicholson, A.: A systematic review of natural flood management modelling: Approaches, limitations, and potential solutions, *J. Flood Risk Manage.*, 163, e12899, <https://doi.org/10.1111/jfr3.12899>, 2023.
- Hudson, P. F., Middelkoop, H., and Stouthamer, E.: Flood management along the Lower Mississippi and Rhine Rivers (The Netherlands) and the continuum of geomorphic adjustment, *Geomorphology*, 1, 209–236, <https://doi.org/10.1016/j.geomorph.2008.07.001>, 2008.
- Jeffries, R., Darby, S. E., and Sear, D. A.: The influence of vegetation and organic debris on flood-plain sediment dynamics: Case study of a low-order stream in the New Forest, England, *Geomorphology*, 51, 61–80, [https://doi.org/10.1016/S0169-555X\(02\)00325-2](https://doi.org/10.1016/S0169-555X(02)00325-2), 2003.
- Keys, T. A., Govenor, H., Jones, C. N., Hession, W. C., Hester, E. T., and Scott, D. T.: Effects of large wood on floodplain connectivity in a headwater Mid-Atlantic stream, *Ecol. Eng.*, 118, 134–142, <https://doi.org/10.1016/j.ecoleng.2018.05.007>, 2018.
- Kitts, D. R.: The hydraulic and hydrological performance of large wood accumulation in a low-order forest stream, PhD thesis, University of Southampton, 367 pp., <http://eprints.soton.ac.uk/id/eprint/185791> (last access: 1 May 2024), 2010.
- Lane, S. N.: Natural Flood Management, *WIRES Water*, 4, e1211, <https://doi.org/10.1002/wat2.1211>, 2017.
- Lashford, C., Lavers, T., Reaney, S., Charlesworth, S., Burgess-Gamble, L., and Dale, J.: Sustainable Catchment-Wide Flood Management: A Review of the Terminology and Application of Sustainable Catchment Flood Management Techniques in the UK, *Water*, 14, 1204, <https://doi.org/10.3390/w14081204>, 2022.
- Leakey, S., Hewett, C. J. M., Glenis, V., and Quinn, P. F.: Modelling the Impact of Leaky Barriers with a 1D Godunov-Type Scheme for the Shallow Water Equations, *Water*, 122, 371, <https://doi.org/10.3390/w12020371>, 2020.
- Li, C., Wang, M., Chen, F., Coulthard, T. J., and Wang, L.: Integrating the SLIDE model within CAESAR-Lisflood: Modeling the ‘rainfall-landslide-flash flood’ disaster chain mechanism under landscape evolution in a mountainous area, *Catena*, 227, 107124, <https://doi.org/10.1016/j.catena.2023.107124>, 2023.
- Liu, Y. B., Gebremeskel, S., de Smedt, F., Hoffmann, L., and Pfister, L.: Simulation of flood reduction by natural river rehabilitation using a distributed hydrological model, *Hydrol. Earth Syst. Sci.*, 86, 1129–1140, <https://doi.org/10.5194/hess-8-1129-2004>, 2004.

- Livers, B., Lininger, K. B., Kramer, N., and Sendrowski, A.: Porosity problems: Comparing and reviewing methods for estimating porosity and volume of wood jams in the field, *Earth Surf. Proc. Land.*, 4513, 3336–3353, <https://doi.org/10.1002/esp.4969>, 2020.
- Lo, H. W., Smith, M., Klaar, M., and Woulds, C.: Potential secondary effects of in-stream wood structures installed for natural flood management: A conceptual model, *WIREs Water*, 85, e1546, <https://doi.org/10.1002/wat2.1546>, 2021.
- Lo, H. W., van Leeuwen, Z., Klaar, M., Woulds, C., and Smith, M.: Geomorphic effects of natural flood management woody dams in upland streams, *River Res. Appl.*, 38, 1787–1802, <https://doi.org/10.1002/rra.4045>, 2022.
- Meadows, T.: Forecasting long-term sediment yield from the upper North Fork Toulte River, Mount St. Helens, USA, PhD thesis, University of Nottingham, 393 pp., <https://eprints.nottingham.ac.uk/id/eprint/27800> (last access: 1 May 2024), 2014.
- Metcalfe, P., Beven, K., Hankin, B., and Lamb, R.: A modelling framework for evaluation of the hydrological impacts of nature-based approaches to flood risk management, with application to in-channel interventions across a 29-km² scale catchment in the United Kingdom, *Hydrol. Process.*, 319, 1734–1748, <https://doi.org/10.1002/hyp.11140>, 2017.
- Met Office: Met Office Rain Radar Data from the NIMROD System, NCAS British Atmospheric Data Centre, <http://catalogue.ceda.ac.uk/uuid/82adec1f896af6169112d09cc1174499> (last access: 1 May 2024), 2003.
- Meyer-Peter, E. and Müller, R.: Formulas for Bed-Load Transport, Paper No. 2, in: Proceedings of the 2nd Congress, IAHR, 7–9 June 1984, Stockholm, 39–64, <https://resolver.tudelft.nl/uuid:4fda9b61-be28-4703-ab06-43cdc2a21bd7> (last access: 1 May 2024), 1948.
- Muhawenimana, V., Wilson, C. A. M. E., Nefjodova, J., and Cable, J.: Flood attenuation hydraulics of channel-spanning leaky barriers, *J. Hydrol.*, 596, 125731, <https://doi.org/10.1016/j.jhydrol.2020.125731>, 2021.
- Muhawenimana, V., Follett, E., Maddock, I., and Wilson, C. A. M. E.: Field-based monitoring of in-stream leaky barrier backwater and storage during storm events, *J. Hydrol.*, 622, 129744, <https://doi.org/10.1016/j.jhydrol.2023.129744>, 2023.
- Newson, M., Lewin, J., and Raven, P.: River science and flood risk management policy in England, *Prog. Phys. Geogr.*, 46, 105–123, <https://doi.org/10.1177/03091333211036384>, 2021.
- Nicholson, A. R., Wilkinson, M. E., O'Donnell, G. M., and Quinn, P. F.: Runoff attenuation features: A sustainable flood mitigation strategy in the Belford catchment, UK, *Area*, 444, 463–469, <https://doi.org/10.1111/j.1475-4762.2012.01099.x>, 2012.
- Nicholson, A. R., O'Donnell, G. M., Wilkinson, M. E., and Quinn, P. F.: The potential of runoff attenuation features as a Natural Flood Management approach, *J. Flood Risk Manage.*, 13, e12565, <https://doi.org/10.1111/jfr3.12565>, 2019.
- Nisbet, T., Roe, P., Marrington, S., Thomas, H., Broadmeadow, S., and Valatin, G.: Project RMP5455: Slowing the Flow at Pickering Final Report: Phase II, Dep. Environ. Food Rural Aff., UK, https://cdn.forestryresearch.gov.uk/2022/02/fr_stf_pickering_p2_may2015_mwh9jja.pdf (last access: 1 May 2024), 2015.
- Norbury, M., Phillips, H., Macdonald, N., Brown, D., Boothroyd, R., Wilson, C., Quinn, P., and Shaw, D.: Quantifying the hydrological implications of pre- and post-installation willowed engineered log jams in the Pennine Uplands, NW England, *J. Hydrol.*, 603, 126855, <https://doi.org/10.1016/j.jhydrol.2021.126855>, 2021.
- O'Callaghan, J. F. and Mark, D. M.: The extraction of drainage networks from digital elevation data, *Comput. Vis. Graph. Image Process.*, 283, 323–344, [https://doi.org/10.1016/S0734-189X\(84\)80011-0](https://doi.org/10.1016/S0734-189X(84)80011-0), 1984.
- Ockelford, A., Wohl, E., Ruiz-Villanueva, V., Comiti, F., Piégay, H., Darby, S., Parsons, D., Yochum, S. E., Wolstenholme, J., White, D., Uno, H., Triantafyllou, S., Stroth, T., Smerdel, T., Scott, D. N., Scamardo, J. E., Rees, J., Rathburn, S., Morrison, R. R., Milan, D., Marshall, A., Lininger, K. B., Kemper, J. T., Karpach, M., Johaneman, T., Iskin, E., Gibaja del Hoyo, J., Hortobágyi, B., Hinshaw, S., Heath, J., Emmanuel, T., Dunn, S., Christensen, N., Beeby, J., Ash, J., Ader, E., and Aarnink, J.: Working with wood in rivers in the Western United States, *River Res. Appl.*, 40, 1626–1641, <https://doi.org/10.1002/rra.4331>, 2024.
- Odoni, N. A. and Lane, S. N.: Assessment of the Impact of Upstream Land Management Measures on Flood Flows in Pickering Beck using Overflow, Forest Research, https://cdn.forestryresearch.gov.uk/2022/02/stfap_final_report_appendix12_2_apr2011.pdf (last access: 1 May 2024), 2010.
- Ordnance Survey: OS Terrain 5 DTM [ASC geospatial data], Scale 1 : 20000, Tiles: Dalby Forest, Updated: April 2020, Ordnance Survey, <http://digimap.edina.ac.uk/> (last access: 1 May 2024), 2020.
- Pearson, E. G.: Modelling the interactions between geomorphological processes and Natural Flood Management, PhD thesis, University of Leeds, 251 pp., <https://etheses.whiterose.ac.uk/id/eprint/29444/> (last access: 1 May 2024), 2020.
- Pinter, N., Ickes, B. S., Wlosinski, J. H., and van der Ploeg, R. R.: Trends in flood stages: Contrasting results from the Mississippi and Rhine River systems, *J. Hydrol.*, 331, 554–566, <https://doi.org/10.1016/j.jhydrol.2006.06.013>, 2006.
- Pinto, C., Ing, R., Browning, B., Delboni, V., Wilson, H., Martyn, D., and Harvey, G. L.: Hydromorphological, hydraulic and ecological effects of restored wood: findings and reflections from an academic partnership approach, *Water Environ. J.*, 333, 353–365, <https://doi.org/10.1111/wej.12457>, 2019.
- Quinn, P. F., Hewett, C. J. M., Wilkinson, M. E., and Adams, R.: The Role of Runoff Attenuation Features (RAFs) in Natural Flood Management, *Water*, 14, 3807, <https://doi.org/10.3390/w14233807>, 2022.
- Ramirez, J. A., Zischg, A. P., Schürmann, S., Zimmermann, M., Weingartner, R., Coulthard, T., and Keiler, M.: Modeling the geomorphic response to early river engineering works using CAESAR-Lisflood, *Anthropocene*, 32, 100266, <https://doi.org/10.1016/j.ancene.2020.100266>, 2020.
- Rasche, D., Reinhardt-Imjela, C., Schulte, A., and Wenzel, R.: Hydrodynamic simulation of the effects of stable in-channel large wood on the flood hydrographs of a low mountain range creek, Ore Mountains, Germany, *Hydrol. Earth Syst. Sci.*, 2310, 4349–4365, <https://doi.org/10.5194/hess-23-4349-2019>, 2019.
- Ravazzolo, D., Spreitzer, G., Tunncliffe, J., and Friedrich, H.: The Effect of Large Wood Accumulations With Rootwads on Local Geomorphic Changes, *Water Resour. Res.*, 58, e2021WR031403, <https://doi.org/10.1029/2021WR031403>, 2022.

- Schalko, I., Lageder, C., Schmocker, L., Weitbrecht, V., and Boes, R. M.: Laboratory Flume Experiments on the Formation of Spanwise Large Wood Accumulations: Part II – Effect on local scour, *Water Resour. Res.*, 55, 4871–4885, <https://doi.org/10.1029/2019WR024789>, 2019.
- Schoorl, J. M., Sonneveld, M. P. W., and Veldkamp, A.: Three-dimensional landscape process modelling: the effect of DEM resolution, *Earth Surf. Proc. Land.*, 259, 1025–1034, [https://doi.org/10.1002/1096-9837\(200008\)25:9<1025::AID-ESP116>3.0.CO;2-Z](https://doi.org/10.1002/1096-9837(200008)25:9<1025::AID-ESP116>3.0.CO;2-Z), 2000.
- Sear, D. A., Millington, C. E., Kitts, D. R., and Jeffries, R.: Logjam controls on channel: floodplain interactions in wooded catchments and their role in the formation of multi-channel patterns, *Geomorphology*, 116, 305–319, <https://doi.org/10.1016/j.geomorph.2009.11.022>, 2010.
- Senior, J. G., Trigg, M. A., and Willis, T.: Physical representation of hillslope leaky barriers in 2D hydraulic models: A case study from the Calder Valley, *J. Flood Risk Manage.*, 153, e12821, <https://doi.org/10.1111/jfr3.12821>, 2022.
- SEPA: Natural Flood Management Handbook, <https://www.sepa.org.uk/media/163560/sepa-natural-flood-management-handbook1.pdf> (last access: 1 May 2024), 2015.
- Shields Jr., F. D. and Gippel, C. J.: Prediction of effects of woody debris removal on flow resistance, *J. Hydraul. Eng.*, 1214, 341–354, [https://doi.org/10.1061/\(ASCE\)0733-9429\(1995\)121:4\(341\)](https://doi.org/10.1061/(ASCE)0733-9429(1995)121:4(341)), 1995.
- Skinner, C. J. and Coulthard, T. J.: Testing the sensitivity of the CAESAR-Lisflood landscape evolution model to grid cell size, *Earth Surf. Dynam.*, 11, 695–711, <https://doi.org/10.5194/esurf-11-695-2023>, 2023.
- Skinner, C. J., Coulthard, T. J., Schwanghart, W., van de Wiel, M. J., and Hancock, G.: Global sensitivity analysis of parameter uncertainty in landscape evolution models, *Geosci. Model Dev.*, 1112, 4873–4888, <https://doi.org/10.5194/gmd-11-4873-2018>, 2018.
- Skinner, C. J., Peleg, N., Quinn, N., Coulthard, T. J., Molnar, P., and Freer, J.: The impact of different rainfall products on landscape modelling simulations, *Earth Surf. Proc. Land.*, 4511, 2512–2523, <https://doi.org/10.1002/esp.4894>, 2020.
- Stewart, E. J., Jones, D. A., Svensson, C., Morris, D. G., Dempsey, P., Dent, J. E., Collier, C. G., and Anderson, C. W.: Reservoir safety – Long return period rainfall, Volume 1, Technical Report (Part 1), Project: FD2613 WS 194/2/39, Department for Environment, Food and Rural Affairs, https://assets.publishing.service.gov.uk/media/602e43e2e90e0709e3127489/long_return_report_1.pdf (last access: 1 May 2024), 2013.
- Thomas, H. and Nisbet, T.: Modelling the hydraulic impact of reintroducing large woody debris into watercourses, *J. Flood Risk Manage.*, 52, 164–174, <https://doi.org/10.1111/j.1753-318X.2012.01137.x>, 2012.
- van Leeuwen, Z. R., Klaar, M. J., Smith, M. W., and Brown, L. E.: Quantifying the natural flood management potential of leaky dams in upland catchments, Part II: Leaky dam impacts on flood peak magnitude, *J. Hydrol.*, 628, 130449, <https://doi.org/10.1016/j.jhydrol.2023.130449>, 2024.
- Villamizar, M. L., Stoate, C., Biggs, J., Szczur, J., Williams, P., and Brown, C. D.: A model for quantifying the effectiveness of leaky barriers as a flood mitigation intervention in an agricultural landscape, *River Res. Appl.*, 40, 365–378, <https://doi.org/10.1002/rra.4241>, 2024.
- Walsh, P., Jakeman, A., and Thompson, C.: Modelling headwater channel response and suspended sediment yield to in-channel large wood using the Caesar-Lisflood landscape evolution model, *Geomorphology*, 363, 107209, <https://doi.org/10.1016/j.geomorph.2020.107209>, 2020.
- Wenzel, R., Reinhardt-Imjela, C., Schulte, A., and Bölscher, J.: The potential of in-channel large woody debris in transforming discharge hydrographs in headwater areas Ore Mountains, Southeastern Germany, *Ecol. Eng.*, 71, 1–9, <https://doi.org/10.1016/j.ecoleng.2014.07.004>, 2014.
- Wilcock, P. R. and Crowe, J. C.: Surface-based Transport Model for Mixed-Size Sediment, *J. Hydraul. Eng.*, 1292, 120–128, [https://doi.org/10.1061/\(ASCE\)0733-9429\(2003\)129:2\(120\)](https://doi.org/10.1061/(ASCE)0733-9429(2003)129:2(120)), 2003.
- Wohl, E.: Floodplains and wood, *Earth-Sci. Rev.*, 123, 194–212, <https://doi.org/10.1016/j.earscirev.2013.04.009>, 2013.
- Wohl, E.: Bridging the gaps: An overview of wood across time and space in diverse rivers, *Geomorphology*, 279, 3–26, <https://doi.org/10.1016/j.geomorph.2016.04.014>, 2017.
- Wohl, E. and Beckman, N. D.: Leaky rivers: Implications of the loss of longitudinal fluvial disconnectivity in headwater streams, *Geomorphology*, 205, 27–35, <https://doi.org/10.1016/j.geomorph.2011.10.022>, 2014.
- Wohl, E., Kramer, N., Ruiz-Villanueva, V., Scott, D. N., Comiti, F., Gurnell, A. M., Piegay, H., Lininger, K. B., Jaeger, K. L., Walters, D. M., and Fausch, K. D.: The natural wood regime in rivers, *BioScience*, 69, 259–273, <https://doi.org/10.1093/biosci/biz013>, 2019.
- Wohl, E., Uno, H., Dunn, S. B., Kemper, J. T., Marshall, A., Means-Brous, M., Scamardo, J. E., and Triantafyllou, S. P.: Why wood should move in rivers, *River Res. Appl.*, 40, 976–987, <https://doi.org/10.1002/rra.4114>, 2023.
- Wolstenholme, J.: Monitoring and modelling fluvial hydrogeomorphic response to leaky wooden dams, PhD thesis, University of Hull, 227 pp., <https://hull-repository.worktribe.com/output/4436310> (last access: 1 May 2024), 2023.
- Wolstenholme, J. M., Skinner, C. J., Milan, D. J., Thomas, R. E., and Parsons, D. R.: Localised geomorphic response to channel-spanning leaky wooden dams, *EGU Sphere* [preprint], <https://doi.org/10.5194/egusphere-2024-3001>, 2024a.
- Wolstenholme, J. M., Skinner, C. J., Milan, D., Thomas, R. E., and Parsons, D. R.: CAESAR-Lisflood 1.9j LD, Zenodo [code and data set], <https://doi.org/10.5281/zenodo.12795495>, 2024b.
- Wong, J. S., Freer, J. E., Bates, P. D., Warburton, J., and Coulthard, T. J.: Assessing the hydrological and geomorphic behaviour of a landscape evolution model within a limits-of-acceptability uncertainty analysis framework, *Earth Surf. Proc. Land.*, 46, 1981–2003, <https://doi.org/10.1002/esp.5140>, 2021.
- Xie, J., Coulthard, T. J., and McLelland, S. J.: Modelling the impact of seismic triggered landslide location on basin sediment yield, dynamics and connectivity, *Geomorphology*, 398, 108029, <https://doi.org/10.1016/j.geomorph.2021.108029>, 2022.